ROCKDALE COUNTY, GEORGIA	
PROJECT #:	0013163/0012886
PROJECT:	Sigman Road - Lester Rd to Irwin Bridge Rd
BID NUMBER	

BID SCHEDULE

Item #	GDOT #	Description	Units	Est. Bid Quantity	Unit Price Bid	Total Price Bid
005	150-1000	TRAFFIC CONTROL - 0013163	LS	1		
010	150-1000	TRAFFIC CONTROL - 0012886	LS	1		
015	153-1300	FIELD ENGINEERS OFFICE TP 3	EA	1		
020	156-0100	GPS DATA COLLECTION & SUBMITTAL - 0013163	LS	1		
025	156-0100	GPS DATA COLLECTION & SUBMITTAL - 0012886	LS	1		
030	163-0232	TEMPORARY GRASSING	AC	55		
035	163-0240	MULCH	TN	144		
040	163-0300	CONSTRUCTION EXIT	EA	10		
045	163-0501	CONSTR AND REMOVE SILT CONTROL GATE,TP 1	EA	14		
050	163-0528	CONSTR AND REM FAB CK DAM -TP C SLT FN	LF	1340		
055	163-0529	CNST/REM TEMP SED BAR OR BLD STRW CK DM	LF	3480		
060	163-0540	CONST AND REM RETROFIT, STA NO - 1158+37 - LT	EA	1		
065	163-0540	CONST AND REM RETROFIT, STA NO - 1115+75 - LT	EA	1		
070	163-0540	CONST AND REM RETROFIT, STA NO - 1133+00 - RT	EA	1		
075	163-0540	CONST AND REM RETROFIT, STA NO - 1137+86 - LT	EA	1		
080	163-0540	CONST AND REM RETROFIT, STA NO - 1115+75 - RT	EA	1		
085	163-0540	CONST AND REM RETROFIT, STA NO - 1156+00 - RT	EA	1		
090	163-0540	CONST AND REM RETROFIT, STA NO - 1138+50 - RT	EA	1		
095	163-0540	CONST AND REM RETROFIT, STA NO - 1119+89 - LT	EA	1		
100	163-0541	CONSTR & REM ROCK FILTER DAMS	EA	57		
105	163-0550	CONS & REM INLET SEDIMENT TRAP	EA	81		
110	165-0030	MAINT OF TEMP SILT FENCE, TP C	LF	12018		
115	165-0041	MAINT OF CHECK DAMS - ALL TYPES	LF	670		
120	165-0071	MAINT OF SEDIMENT BARRIER - BALED STRAW	LF	1740		
125	165-0085	MAINT OF SILT CONTROL GATE, TP 1	EA	14		
130	165-0095	MAINT OF RETROFIT, STA NO - 1158+37 - LT	EA	1		
135	165-0095	MAINT OF RETROFIT, STA NO - 1138+50 - RT	EA	1		
140	165-0095	MAINT OF RETROFIT, STA NO - 1137+86 - LT	EA	1		
145	165-0095	MAINT OF RETROFIT, STA NO - 1133+00 - RT	EA	1		
150	165-0095	MAINT OF RETROFIT, STA NO - 1119+89 - LT	EA	1		
155	165-0095	MAINT OF RETROFIT, STA NO - 1115+75 - LT	EA	1		
160	165-0095	MAINT OF RETROFIT, STA NO - 1156+00 - LT	EA	1		
165	165-0095	MAINT OF RETROFIT, STA NO - 1115+75 - RT	EA	1		
170	165-0101	MAINT OF CONST EXIT	EA	10		

COMPANY NAME: _____

Failure to return this page my result in rejection of bid.

ROCKDALE COUNTY, GEORGIA	
PROJECT #:	0013163/0012886
PROJECT:	Sigman Road - Lester Rd to Irwin Bridge Rd
BID NUMBER	

BID SCHEDULE

Item #	GDOT #	Description	Units	Est. Bid Quantity	Unit Price Bid	Total Price Bid
175	165-0105	MAINT OF INLET SEDIMENT TRAP	EA	81		
180	165-0110	MAINT OF ROCK FILTER DAM	EA	29		
185	167-1000	WATER QUALITY MONITORING AND SAMPLING	EA	3		
190	167-1500	WATER QUALITY INSPECTIONS	MO	24		
195	171-0030	TEMPORARY SILT FENCE, TYPE C	LF	18866		
200	207-0203	FOUND BKFILL MATL, TP II	CY	26		
205	208-0200	ROCK EMBANKMENT	CY	112		
210	210-0100	GRADING COMPLETE - 0013163	LS	1		
215	210-0100	GRADING COMPLETE - 0012886	LS	1		
220	212-1000	GRANULAR EMBANKMENT INCL M&H	CY	18000		
225	310-1101	GR AGGR BASE CRS, INCL MATL	TN	26080		
230	318-3000	AGGR SURF CRS	TN	825		
235	402-1812	RECYL AC LEVELING,INC BM&HL	TN	6248		
240	402-3121	RECYL AC 25MM SP,GP1/2,BM&HL	TN	14386		
245	402-3130	RECYL AC 12.5MM SP,GP2,BM&HL	TN	4063		
250	402-3190	RECYL AC 19 MM SP,GP 1 OR 2 ,INC BM&HL	TN	4874		
255	413-0750	TACK COAT	GL	3443		
260	432-5010	MILL ASPH CONC PVMT,VARB DEPTH	SY	1335		
265	441-0016	DRIVEWAY CONCRETE, 6 IN TK	SY	914		
270	441-0018	DRIVEWAY CONCRETE, 8 IN TK	SY	188		
275	441-0104	CONC SIDEWALK, 4 IN	SY	9714		
280	441-0108	CONC SIDEWALK, 8 IN	SY	500		
281	441-0300	CONC SPILLWAY, SPCL DES	EA	27		
285	441-0748	CONC MEDIAN, 6 IN	SY	1899		
290	441-3999	CONCRETE V GUTTER	LF	857		
295	441-4020	CONC VALLEY GUTTER, 6 IN	SY	739		
300	441-6222	CONC CURB & GUTTER/ 8X30TP2	LF	15200		
305	441-6740	CONC CURB & GUTTER/ 8X30 TP7	LF	12000		
310	444-1000	SAWED JTS IN EXIST PVMTS - PCC	LF	308		
315	446-1100	PVMT REF FAB STRIPS, TP2,18 INCH WIDTH	LF	2600		
320	455-1000	FILTER FAB/EMBANKMENT STAB	SY	550		
325	500-3101	CLASS A CONCRETE	CY	67		
330	500-3120	CLASS A CONCRETE, TYPE P3, RETAINING WALL	LF	383		
335	500-3200	CL B CONC SPL DES FLUMES	CY			

COMPANY NAME: _____

Failure to return this page my result in rejection of bid.

ROCKDALE COUNTY, GEORGIA	
PROJECT #:	0013163/0012886
PROJECT:	Sigman Road - Lester Rd to Irwin Bridge Rd
BID NUMBER	

BID SCHEDULE

Item #	GDOT #	Description	Units	Est. Bid Quantity	Unit Price Bid	Total Price Bid
340	500-9999	CL B CONC,BASE OR PVMT WIDEN	CY	18		
345	511-1000	BAR REINF STEEL	LB	4774		
350	550-1180	STM DR PIPE 18,H 1-10	LF	4759		
355	550-1240	STM DR PIPE 24,H 1-10	LF	723		
360	550-1300	STM DR PIPE 30,H 1-10	LF	300		
361	550-1360	STM DR PIPE, 36 IN, H 1-10	LF	40		
365	550-1540	STM DR PIPE 54,H 1-10	LF	105		
370	550-2180	SIDE DR PIPE 18,H 1-10	LF	464		
375	550-3518	SAFETY END SECTION 18,STD,6:1	EA	32		
380	550-4218	FLARED END SECT 18 IN, ST DR	EA	5		
385	550-4224	FLARED END SECT 24 IN, ST DR	EA	1		
390	550-4230	FLARED END SECT 30 IN, ST DR	EA	2		
391	550-4236	FLARED END SECT 36 IN, STORM DRAIN	EA	1		
395	573-2006	UNDDR PIPE INCL DRAIN AGGR 6	LF	2860		
400	603-2024	STN DUMPED RIP RAP, TP 1, 24	SY	32		
405	603-2181	STN DUMPED RIP RAP, TP 3, 18	SY	1412		
410	603-7000	PLASTIC FILTER FABRIC	SY	1444		
415	610-9099	REM WINGWALLS/PARAPETS, STA - STA	LS	1		
420	611-8050	ADJUST MANHOLE TO GRADE WATER	EA	1		
425	611-8050	ADJUST MANHOLE TO GRADE SANITARY SEWER	EA	13		
430	611-8140	ADJUST WATER VALVE BX TO GRADE	EA	14		
435	612-0100	TEMP BARRIER, METHOD NO. 1	LF	1000		
440	627-1000	MSE WALL FACE, 0 - 10 FT HT, WALL NO - 1	SF	668		
445	627-1010	MSE WALL FACE, 10 - 20 FT HT, WALL NO - 1	SF	1528		
450	627-1120	COPING B, WALL NO - 1	LF	193		
455	627-1000	MSE WALL FACE, 0 - 10 FT HT, WALL NO - 3	SF	887		
460	627-1010	MSE WALL FACE, 10 - 20 FT HT, WALL NO - 3	SF	486		
465	627-1120	COPING B, WALL NO - 3	LF	145		
470	627-1000	MSE WALL FACE, 0 - 10 FT HT, WALL NO - 4	SF	324		
475	627-1010	MSE WALL FACE, 10 - 20 FT HT, WALL NO - 4	SF	553		
480	627-1120	COPING B, WALL NO - 4	LF	104		
485	627-1000	MSE WALL FACE, 0 - 10 FT HT, WALL NO - 6	SF	629		
490	627-1010	MSE WALL FACE, 10 - 20 FT HT, WALL NO - 6	SF	4013		
495	627-1020	MSE WALL FACE, 20 - 30 FT HT, WALL NO - 6	SF	2395		

COMPANY NAME: _____

Failure to return this page my result in rejection of bid.

ROCKDALE COUNTY, GEORGIA	
PROJECT #:	0013163/0012886
PROJECT:	Sigman Road - Lester Rd to Irwin Bridge Rd
BID NUMBER	

BID SCHEDULE

Item #	GDOT #	Description	Units	Est. Bid Quantity	Unit Price Bid	Total Price Bid
500	627-1120	COPING B, WALL NO - 6	LF	452		
505	628-0100	PERMANENT SOIL-NAILED WALL 7	LS	1		
510	628-0100	PERMANENT SOIL-NAILED WALL 8	LS	1		
515	627-1000	MSE WALL FACE, 0 - 10 FT HT, WALL NO - 9	SF	115		
520	627-1010	MSE WALL FACE, 10 - 20 FT HT, WALL NO - 9	SF	2753		
525	627-1020	MSE WALL FACE, 20 - 30 FT HT, WALL NO - 9	SF	2600		
530	627-1120	COPING B, WALL NO - 9	LF	311		
535	627-1000	MSE WALL FACE, 0 - 10 FT HT, WALL NO - 10	SF	792		
540	627-1010	MSE WALL FACE, 10 - 20 FT HT, WALL NO - 10	SF	2482		
545	627-1020	MSE WALL FACE, 20 - 30 FT HT, WALL NO - 10	SF	408		
550	627-1120	COPING B, WALL NO - 10	LF	296		
555	632-0003	CHANGEABLE MESS SIGN,PORT,TP 3	EA	4		
560	634-1200	RIGHT OF WAY MARKERS	EA	148		
565	636-1033	HWY SIGNS, TP1MAT,REFL SH TP 9	SF	140		
570	636-1036	HWY SGN,TP1MAT,REFL SH TP 11	SF	307		
575	636-1045	HWY SGN,TP2,REFL SH TP 11	SF	85		
580	636-2070	GALV STEEL POSTS, TP 7	LF	50		
585	636-2080	GALV STEEL POSTS, TP 8	LF	746.5		
590	639-5000	PRESTRESSED CONC STR POLE, TP- IV	EA	8		
595	641-1100	GUARDRAIL, TP T	LF	290		
600	641-1200	GUARDRAIL, TP W	LF	1337		
605	641-5001	GUARDRAIL ANCHORAGE, TP 1	EA	8		
610	641-5015	GUARDRL ANCHOR, TP 12A, 31 IN, TANG, E/A	EA	3		
615	641-5025	GUARDRL ANCHOR, TP12C,31IN,FLR,NON-E/A	EA	2		
620	643-0010	FIELD FENCE WOVEN WIRE	LF	1202		
625	643-1132	CH LK FEN,ZC COAT, 4', 9 GA	LF	660		
630	643-1152	CH LK FEN,ZC COAT, 6', 9 GA	LF	3128		
635	643-8010	GATE, CHAIN LINK ZC COAT - 16-FT	EA	1		
640	643-8040	GATE, WOVEN WIRE - 12-FT	EA	10		
645	643-8200	BARRIER FENCE (ORANGE), 4 FT	LF	1300		
650	647-1000	TRAF SIGNAL INSTALLATION NO - SIGNAL #1- SIGMAN RD @ ROCKBRIDGE	LS	1		
655	647-1000	TRAF SIGNAL INSTALLATION NO - SIGNAL #2- SIGMAN RD @ IRWIN BR RD	LS	1		
660	653-0120	THERM PVMT MARK, ARROW, TP 2	EA	52		
665	653-0160	THERM PVMT MARK, ARROW, TP 6	EA	6		

COMPANY NAME: _____

Failure to return this page my result in rejection of bid.

ROCKDALE COUNTY, GEORGIA	
PROJECT #:	0013163/0012886
PROJECT:	Sigman Road - Lester Rd to Irwin Bridge Rd
BID NUMBER	

BID SCHEDULE

Item #	GDOT #	Description	Units	Est. Bid Quantity	Unit Price Bid	Total Price Bid
670	653-0170	THERM PVMT MARK, ARROW, TP 7	EA	8		
675	653-0210	THERM PVMT MARK, WORD , TP 1	EA	5		
680	653-8025	WET WEATHER THERM SOLID TRAF STRIPE, 5 IN, WHITE	LM	4.183		
685	653-8030	WET WEATHER THERMO SOLID TRAF STRIPE, 5 IN, YELLO	LM	2.5		
690	653-8070	WET WEATHER THERMO SOLID TRAF STRIPE, 8 IN, WHITE	LF	3770		
695	653-8050	WET WEATHER THERMO SKIP TRAF STRIPE, 5 IN, WHITE	GLM	2.458		
700	653-8085	WET WEATHER THERMO SOLID TRAF STRIPE, 24 IN, WHITI	LF	3770		
705	653-8090	WET WEATHER THERMO TRAF STRIPE, WHITE	SY	1035		
710	653-8095	WET WEATHER THERMO TRAF STRIPE, YELLOW	SY	545		
715	654-1001	RAISED PVMT MARKERS TP 1	EA	110		
720	654-1003	RAISED PVMT MARKERS TP 3	EA	580		
725	659-7015	H/A PRF PLS PM, BIKE LN MKG. TP P	EA	14		
730	660-1225	SEWER FORCE MAIN, 8 IN, - PIPE	LF	460		
735	668-1100	CATCH BASIN, GP 1	EA	37		
740	668-2100	DROP INLET, GP 1	EA	26		
745	668-2110	DROP INLET, GP 1, ADDL DEPTH	LF	5		
750	668-4300	STORM SEW MANHOLE, TP 1	EA	1		
755	668-5000	JUNCTION BOX	EA	1		
760	670-0535	BUTTERFLY VALVE, 24 IN	EA	1		
765	670-1060	WATER MAIN, 6 IN	LF	200		
770	670-1080	WATER MAIN, 8 IN	LF	200		
775	670-1120	WATER MAIN, 12 IN	LF	240		
780	670-1240	WATER MAIN, 24 IN	LF	1160		
785	670-1600	CUT & PLUG EXIST WATER MAIN	EA	2		
790	670-2002	VALVE MARKER	EA	16		
795	670-2120	GATE VALVE, 12 IN	EA	2		
800	670-2500	INSERTION VALVE - 24"	EA	2		
805	670-3015	TAPPING SLV/VALVE ASMBLY, - 24"X8"	EA	2		
810	670-4000	FIRE HYDRANT	EA	2		
815	670-4500	CONC THRUST COLLAR, 6" PIPE OR SMALLER	EA	2		
820	670-4520	CONC THRUST COLLAR, 12" PIPE	EA	2		
825	670-5010	WATER SERVICE LINE, 1 IN	LF	25		
830	670-5020	WATER SERVICE LINE, 2 IN	LF	75		
835	670-5620	WATER SERVICE LINE, 3/4 IN	LF	130		

COMPANY NAME: _____

Failure to return this page my result in rejection of bid.

ROCKDALE COUNTY, GEORGIA	
PROJECT #:	0013163/0012886
PROJECT:	Sigman Road - Lester Rd to Irwin Bridge Rd
BID NUMBER	

BID SCHEDULE

Item #	GDOT #	Description	Units	Est. Bid Quantity	Unit Price Bid	Total Price Bid
840	670-9710	RELOCATE EXIST FIRE HYDRANT	EA	8		
845	670-9730	RELOCATE X WATER METER,INC BOX 5/8"	EA	16		
850	670-9736	RLC EX WTR MTR INC BP&VLT,LT4"	EA	3		
855	670-9737	RLC EXT WT MT, INC BP&VLT, 4"GT	EA	3		
860	670-9920	REMOVE EXIST FIRE HYDRANT	EA	1		
865	681-4211	LT STD, 32 FT MH, POST TOP	EA	93		
870	681-6290	LUMINAIRE, TP 3, LED	EA	93		
875	682-1405	CABLE, TP XHHW, AWG NO 8	LF	17000		
880	682-1408	CABLE, TP XHHW, AWG NO 2	LF	53000		
885	682-6222	CONDUIT, NONMETL, TP 2, 2 IN	LF	16000		
890	682-6225	CONDUIT, NONMETL, TP 2, 2 1/2 IN	LF	50		
895	682-6233	CONDUIT, NONMETL, TP 3, 2 IN	LF	120		
900	682-9000	MAIN SVC PICK UP POINT POINT C	LS	1		
905	682-9022	ELEC JCT BX,REF PLASTIC MORTAR METAL	EA	12		
910	682-9950	DIRECTIONAL BORE - 3 INCH - SIGNALS	LF	120		
915	682-9950	DIRECTIONAL BORE - 3 INCH	LF	2200		
920	687-1000	TRAFFIC SIGNAL TIMING - SIGNAL # 1	LS	1		
925	687-1000	TRAFFIC SIGNAL TIMING - SIGNAL # 2	LS	1		
930	700-6910	PERMANENT GRASSING 0013163	AC	25		
935	700-7000	AGRICULTURAL LIME	TN	53		
940	700-8000	FERTILIZER MIXED GRADE	TN	22		
945	700-8100	FERTILIZER NITROGEN CONTENT	LB	1146		
950	700-9300	SOD	SY	90		
955	716-2000	EROSION CONTROL MATS, SLOPES	SY	7603		
960	926-2500	3G / 4G CELL ROUTER TP - 4	EA	2		
965	999-3110	DETENTION POND	EA	7		
970	999-3156	ENHANCED DRY SWALE	LF	3603		
					TOTAL	

CERTIFICATION OF NONCOLLUSION IN BID PREPARATION_____

(Signature) (Date)

The County requires that all who enter into a contract for the physical performance of services with the County must satisfy O.C.G.A. § 13-10-91 and Rule 300-10-1-.02, in a manner, and such are conditions of the contract.

COMPANY NAME: _____

Failure to return this page my result in rejection of bid.

ROCKDALE COUNTY, GEORGIA	
PROJECT #:	0013163/0012886
PROJECT:	Sigman Road - Lester Rd to Irwin Bridge Rd
BID NUMBER	

BID SCHEDULE

Item #	GDOT #	Description	Units	Est. Bid Quantity	Unit Price Bid	Total Price Bid

In compliance with the attached specifications, the undersigned offers and agrees, if this bid is accepted by the Board of Commissioners within ninety (90) days of the date of bid opening, to furnish any or all of the items upon which prices are quoted within the time specified in the bid schedule. By submission of this bid, I understand that Gwinnett County uses Electronic Payments for remittance of goods and services. Vendors should select their preferred method of electronic payment upon notice of award. For more information on electronic payments, please refer to the Electronic Payment information in the Instructions to Bidders.

LEGAL BUSINESS NAME: _____

(If your company is an LLC, you must identify all principals to include address and phone numbers in your submittal)

FED TAX ID_____

ADDRESS: _____

DOES YOUR COMPANY CURRENTLY HAVE A LOCATION WITHIN GWINNETT COUNTY? YES ☐ NO ☐

REPRESENTATIVE SIGNATURE: _____

PRINT AUTHORIZED REPRESENTATIVE'S NAME: _____

TELEPHONE NUMBER: _____ FAX: _____

E-MAIL ADDRESS_____

COMPANY NAME: _____

Failure to return this page my result in rejection of bid.